



No. UEV/08 /418 of 2020  
Mumbai - 400 098  
Date: 29/07/2020

### TENDER NOTICE

Wax sealed tenders are invited by the University Engineer, University of Mumbai for the following work:

- 1 Name of work : Repairing, painting, sliding window and flooring in Room no 306 at Life Science building on 3<sup>rd</sup> floor, Vidyanagari Campus, University of Mumbai, Mumbai-400 098
- 2 Cost put to tender : Rs. 2,28,846/- (Excluding all the Taxes) (
- 3 Cost of Tender form : Rs. 224/- (200 + 12% GST) only
- 4 Date for issuing of tender form : On 4/8/2020 after 11:00 AM
- 5 Last date for issuing and submission of tender form : On 11/8/2020 before 1:00 PM
- 6 Place and time for payment of tender form fees : University cash counter, Examination House, 2<sup>nd</sup> floor, Room no-45 Vidyanagari Campus
- 7 Place and time of availability of 'Tender' : Office of University Engineer, Dr. Ambedkar Bhavan, 1<sup>st</sup> floor, Vidyanagari Campus.
- 8 Place for submission of 'Tender' : Office of University Engineer, Dr. Ambedkar Bhavan, 1<sup>st</sup> floor, Vidyanagari Campus.
- 9 Mode of payment of R.M.D. : R.M.D. will be 5% of work will be deducted in bill and return after defect liability period expired
- 10 Period within which work is to be done : 1 Month after issue of work order
- 11 Defect liability period : 1 Year

The blank tender form (Schedule "B") must be submitted and details such as (i) Tender Fee Receipt No. & Date must invariably be written on it.

The contractor in the field should be PWD registered. The rate should include all the taxes like GST. Any over writing in tender document leads to rejection of tender.

Please note that, if any damages are done to electrical wiring, cabling etc. and internal, external pipeline during the repairing work shall be rectified / replaced by the contractor immediately at his own expense.

The selected contractor will have to execute an agreement on Rs. 100/- Stamp paper. University of Mumbai will not be responsible for any postal delay/loss in transit.

University Engineer, University of Mumbai reserves the right to reject all the tenders or any tender without assigning any reasons therefore and to relax or waive any of the condition stipulated in any of the tender that may be issued wherever necessary.

  
University Engineer  
University of Mumbai



**ESTIMATE**

**Name of work :** Repairing, painting, sliding window and flooring in Room no 306 at Life Science building on 3rd floor, Vidyanagari campus, University of Mumbai, Mumbai-400 098.

Sr. No.	Item No.	Description	Unit	Rate	Add 5% in rate For Corporation Areas	Quantity	Amount
1	46.19	Removing cement tiles, or marble or polished shahabad floor or dado without bed concrete including stacking the materials as directed with all	Square Metre	36	37.80	38.00	1436.40
2	46.15	Removing doors and windows with frames and stacking the materials as directed with all leads, lifts etc. complete.	Number	125	131.25	8.00	1050.00
3	32.07	Providing internal cement plaster 20mm thick in Single coats in cement mortar 1:4 without neeru finish, to concrete or brick surface, in all positions including scaffolding	Square Metre	392	411.60	10.00	4116.00
4	33.68	Providing and laying telephone black / Amba White / Cadburybrown / Ruby red / Ocean Brown granite stone of 18 to 20 mm thick for door frame/ dado/ window boxing etc. On C.M. 1:6 including filling joints with polymer base filler nosing/moulding the sharp edges wherever necessary, curing, etc. complete.	Square Metre	3933	4129.65	10.00	41296.50

5	39.4	Providing and fixing in position. (as per I.S.1868 / 1982) Aluminium sliding window of two tracks with rectangular pipe having overall dimension 63.50 x 38.10 x 1.02 mm at weight 0.547 kg/Rmt. and window frame bottom track section 61.85 x 31.75 x 1.20 mm at weight 0.695 kg/Rmt. Top and side track section 61.85 x 31.75 x 1.30 mm at weight 0.659 kg/Rmt. The shutter should be of bearing bottom 40 x 18 x 1.25 mm at weight 0.417 kg/Rmt. Inter locking section 40 x 18 x 1.10 mm at weight 0.469 kg/Rmt. And handle section 40 x 18 x 1.25 mm at weight 0.417 kg/Rmt. and top section 40 x 18 x 1.25 mm at weight 0.417 kg/Rmt. As per detailed drawings and as directed by Engineer in charge with all necessary Aluminium sections fixtures and fastenings such as roller bearing in nylon casting	Square Metre	4924	5170.20	6.00	31021.20
6	40.01	Providing and fixing mild steel grill work for windows, ventilators etc. 20 kg/sqm as per drawing including fixtures, necessary welding and painting with one coats of anticorrosive paint and two coats of oil painting complete.	Square Metre	1528	1604.40	8.00	12835.20
7	39.53.a	Providing and fixing in position - ----- aluminium fixed window fully glazed of any size as per detailed drawing and as directed by Engineer in charge with all necessary alluminium sections including necessary fixtures and fastening such as 5 mm thick clear float glass etc. complete. a) Colour anodized	Square Metre	5013	5263.65	2.50	13159.13

8	33.4	Providing and laying vitrified mirror / glossy finish tiles decorative type having size 590 mm to 605 mm x 590 mm to 605 mm of 8 to 10 mm thickness and confirming to IS. 15622-2006 ( group Bla) of approved make, shade and pattern for flooring in required position laid on a bed of 1:4 cement mortar including neat cement float, filling joints, curing and clearing etc. complete.	Square Metre	1027	1078.35	38.00	40977.30
9	37.22	Providing and fixing Shutter to wall Cupboard consisting of Teak Wood styles and Rails 25 mm thick and 75 mm wide with panel insert of 12 mm thick particle Board with one approved coloured Laminated Face on one side 1.5 mm thick, bonded with Phenol Formaldehyde Synthetic Resin including Lipping Beading. Iron oxidised fixtures and fastening and oil primer coat etc. complete. (Excluding cupboard frame).	Square Metre	3173	3331.65	10.00	33316.50
10	37.08	Providing and fixing country teak wood common rafters, purlins and purlin cleats, hip rafters, jack rafters, ridges, wall plates, post plates and posts for roofing etc. including scaffolding, if necessary, all iron work and one coat of primer etc. complete.	Cubic Metre	124701	130936.05	0.10	13093.61


11	41.74	Providing and fixing coloured glazed earthenware Wash Hand Basin of 63 cm x 45 cm size including cold water pillar tap/cold and hot water pillar tap brackets, rubber plugs and brass chain, stop tap and necessary pipe connection including P.V.C. waste pipe and trap up to the outside face of the wall.	Number	5767	6055.35	1.00	6055.35
12	42.57	Providing and fixing on walls/ ceiling/ floor 25 mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	Running Metre	288	302.40	5.00	1512.00
13	42.51	Providing and fixing 75 mm dia stabiliser pipe/ P.V.C. soil vent/waste pipe and with necessary fixtures and fitting such as bends, tees, single junctions, slotted vent, clamps etc. complete	Running Metre	480	504.00	5.00	2520.00
14	42.67	Providing and fixing 10 cm PVC nahani trap with grating etc. complete.	Number	422	443.10	1.00	443.10
15	42.2	Providing and fixing 450mm x 550mm size superior type Belgium mirror with 16mm dia. nickel plated towel rod etc. complete.	Number	703	738.15	1.00	738.15
16	42.31	Providing and fixing chromium plated towel rod 16 mm dia and 75 cm. in length including all accessories complete.	Number	242	254.10	1.00	254.10
17	36.19	Scrapping the old plastered internal surface with sand paper and coating the entire surface with mixture of whiting or glue and linseed oil including scaffolding etc. complete as directed.	Square Metre	28.7	30.14	145.00	4369.58


18	35.21	Providing and applying priming coat on concrete/ masonry/ Asbestos Cement plastered surfaces including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required etc. complete.	Square Metre	30	31.50	145.00	4567.50
19	36.12	Providing and applying plastic emulsion paint of approved quality, colour and shade to old and new surfaces in two coats including scaffolding, preparing the surface. (excluding the primer coat)etc. complete.	Square Metre	66.5	69.83	145.00	10124.63
20	35.19	Providing and applying priming coat over new wood and wood based surfaces, including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter, sand papering and knotting, scaffolding etc. complete.	Square Metre	27	28.35	9.00	255.15
21	35.07	Providing and applying two coats of synthetic enamel paint of approved colour to new /old structural steel work and wood work in buildings, including scaffolding if necessary, cleaning and preparing the surface (excluding primer coat) etc. complete.	Square Metre	79	82.95	9.00	746.55
22	46.59	Lowering down the debris obtained from breaking and removing the cement plaster / burnt brick masonry of the first floor by any means without causing dust nuisance and damage to structure, stacking the same as and where directed including cleaning the site complete.	Cubic metre	603	633.15	4.00	2532.60

23	Add item for DSR 2017-18. Sr.no. - 20	Removing any kind of debris including loading in truck and conveying to dumping point approved by MCGM, unloading, spreading etc. complete. (SSR Transportation page no.362) (Note: rate to be reduced proportionally, if lead is within 50 km).	Cubic metre	577.5	606.38	4.00	2425.50
----	---------------------------------------	--	-------------	-------	--------	------	---------

Total amount	228846.03
<b>Say Amount</b>	<b>228846.00</b>
Add 12%GST	27461.52
Add 0.5%Labour Cess	1144.23
Net amount	257451.75
<b>Say Amount</b>	<b>257452.00</b>


Rs. Two Lakhs Twenty Eight Thousand Eight Hundred Forty Six Only (Excluding all Taxes)

Estimate Prepared By :- 

Estimate Checked By:- 

We quote \_\_\_\_\_ % i.e. \_\_\_\_\_ percentage (In words) above / Below / At Par with estimated cost of Rs. 2,28,846/-

Rubber Stamp of the firm  
(Signature of the contractor)

  
University Engineer  
(University of Mumbai)