



No.UEV/ 55/ 611 of 2020
Mumbai – 400 098
Date: 20/08/2020

TENDER NOTICE

Wax sealed tenders are invited by the University Engineer, University of Mumbai for the following work :

- | | | | |
|----|---|---|--|
| 1 | Name of work | : | Renovation of toilets and W.C in flats B21 and B22 of Class IV quarters at Vidyanagari campus, University of Mumbai, Mumbai-400 098. |
| 2 | Cost put to tender | : | Rs 1,50,663/- excluding all taxes (Rupees One Lakh fifty thousand six hundred and sixty three only) |
| 3 | Cost of Tender form | : | Rs. 224/- (200 + GST) only |
| 4 | Date for issuing of tender form | : | On <u>20/08</u> 2020 after 11:00 AM |
| 5 | Last date for issuing and submission of tender form | : | On <u>27/08</u> 2020 before 1:00 PM |
| 6 | Place and time for payment of tender form fees | : | University cash counter, Examination House, 2 nd floor, Room no-45 Vidyanagari Campus |
| 7 | Place and time of availability of 'Tender' | : | Office of University Engineer, Dr. Ambedkar Bhavan, 1 st floor, Vidyanagari Campus. |
| 8 | Place for submission of 'Tender' | : | Office of University Engineer, Dr. Ambedkar Bhavan, 1 st floor, Vidyanagari Campus. |
| 9 | Mode of payment of R.M.D. | : | R.M.D. will be 5% of work will be deducted in bill and return after defect liability period expired |
| 10 | Period within which work is to be done | : | 15 days after issue of work order |
| 11 | Defect liability period | : | 1 Year |


The blank tender form (Schedule "B") must be submitted and details such as (i) Tender Fee Receipt No. & Date must invariably be written on it.

The contractor in the field should be PWD registered. Any over writing in tender document leads to rejection of tender.

Please note that, if any damages are done to electrical wiring, cabling etc. and internal, external pipeline during the repairing work shall be rectified/replaced by the contractor immediately at his own expense.

The selected contractor will have to execute an agreement on Rs. 100/- Stamp paper. University of Mumbai will not be responsible for any postal delay/loss in transit.

University Engineer, University of Mumbai reserves the right to reject all the tenders or any tender without assigning any reasons therefore and to relax or waive any of the condition stipulated in any of the tender that may be issued wherever necessary.


University Engineer



LAST DATE FOR SUBMISSION OF
TENDER FORM

Challan No. _____ Date: _____

SCHEDULE 'B'

Name of work : Renovation of toilet and W.C of B21 and B22 of Class IV quarters at Vidyanagari campus, University of Mumbai, Mumbai-400 098.

Sr. No.	Item No.	Description	Unit	Rate	Add 5% in rate for Corporation Area	Quantity	Amount
1	46.19	Removing cement tiles, or marble or polished shahabad floor or dado without bed concrete including stacking the materials as directed with all leads, lifts etc. complete	Square Metre	36.36	38.18	43.38	1656.16
2	46.14	Removing brick bat coba including stacking the spoils as directed with all leads, lifts etc. complete.	Cubic metre	512.07	537.67	1.36	731.24
3	46.41	Removing W.C. pans including disconnecting the sanitary and water supply connections, removing and breaking flooring and bed concrete around pan removing the same carefully and stacking the serviceable materials as adn where directed including throwing the unserviceable materials out side etc. carefully and throwing out the refusal outside etc. complete.	Number	166.65	174.98	1	174.98
4	42.33	Providing and fixing 1st class white glazed earthenware Orissa Type W.C. Pan 580 mm dia including P or S trap cast iron soil and vent pipe upto the outside face of the wall (1:5:10) cement concrete bedding 15 mm thick, 10 liter P.V.C. flushing cistern with all necessary pipe connection etc. complete.	Number	6071.11	6374.67	1	6374.67
5	31.26	Providing waterproofing in W.C. and bath including brick bat coba in all position including providing and laying 12mm bedding in cement mortar 1:3 on vergin concrete slab with waterproofing compound @ 1kg/per bag of cement laying brick bat coba of required thickness in cm 1:5 with waterproofing compound 1 kg/bag of cement grouting and finishing the top layer with 20mm thick brick bedding in cement mortar 1:3 with waterproofing compound 1 kg/per bag of cement and testing the treated portion for 48 hours by pond test and covering ten years' guarantee on requisite stamp paper including curing etc complete.	Cubic Metre	5151	5408.55	1.36	7355.63
6	31.05	Providing water proof bedding for flooring of Bath and WC 25 mm thick in C.M. 1:3 including using approved water proofing compound in specified proportion as per manufacturers specifications for per bag of cement including leveling, curing and covering 10 years guarantee on court fee stamp paper of Rs.500/- including ponding test etc. complete.	Square Metre	348.45	365.87	5.76	2107.43
7	31.06	Providing waterproof plaster in W.C. and bath 12 mm thick for dado in cement mortar 1:3 with neat finishing, floating using waterproofing compound at the rate of 1 kg. per bag of cement of approved make and manufacturer and curing etc. complete. (Excluding Tiles) (As directed by Engineer in Charge)	Square Metre	313.1	328.76	41.38	13603.88
8	33.42	Providing and laying vitrified matt fininsh tiles having size 300 mm x 300 mm of 8 to 10 mm thickness and confirming IS. 15622-2006 (Group Bla) of approved make, shade and pattern for flooring in required position laid on a bed of 1:4 cement morar including neat cement float, filling joints, curing and cleaning etc. complete.	Square Metre	1426.12	1497.43	5.76	8625.17
9	33.41	Providing and laying glossy finish tiles having size 375 mm x 300 mm of 8 to 10 mm thickness and confirming to IS 15622-2006 (group Bla) of approved make, shade and pattern for dado and skirting in required position fixed in 1:4 cement mortar including neat cement float, filling joints, curing and clearing etc. complete	Square Metre	1097.87	1152.76	41.38	47701.35

Sr. No.	Item No.	Description	Unit	Rate	Add 5% in rate for Corporation Area	Quantity	Amount
10	46.4	Removing urinal pans or wash hand basins with frame including disconnecting the sanitary and water supply connections, removing the same carefully and stacking the serviceable materials as and where directed including throwing the unserviceable materials outside etc complete	Number	77.77	81.66	2	163.32
11	41.63	Providing and fixing white glazed earthenware Wash Hand Basin of 55cm. x 40 cm. size including cold water pillar tap/cold and hot water pillar tap brackets, rubber plugs and brass chain, stop tap and necessary pipe connections including P.V.C. waste pipe and trap up to the outside face of the wall. Making good the damaged surface, testing etc. complete.	Number	4553.08	4780.73	2	9561.47
12	42.55	Providing and fixing on walls/ ceiling/ floor 15 mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	Running Metre	215.13	225.89	18	4065.96
13	Sr.No. 363 page no.526	Bib cock brass heavy 15mm	number	393.9	413.60	6	2481.57
14	42.67	Providing and fixing 10 cm PVC nahani trap with grating etc. complete.	Number	426.22	447.53	2	895.06
15	39.59	Providing and fixing fiber glass reinforced polyester door shutter 35 mm thick as per IS 14856 (2000) (Reaffirmed 2006) without ventilator including chromium plated fixtures and fastening with chromium plated handles on both sides, etc. complete.	Square Metre	2840.12	2982.13	6.72	20039.89
16	39.68	Providing and fixing in position powder coated aluminium louvered windows / ventilator of various sizes with powder coating as per detailed drawing and specifications including aluminium frames 80 x 38 mm x 1.22 mm box type, 5 mm thick sheet glass louvers, of approved quality etc. complete.	Square Metre	2696.7	2831.54	1.92	5436.55
17	33.48	Providing and fixing green marble of 18 to 20 mm thick for door frame/ dado/ window boxing etc. On C.M. 1:6 including filling joints with polymer base filler nosing the sharp edges wherever necessary, curing, etc. complete.	Square Metre	1841.23	1933.29	7.91	15292.34
18	Add item for DSR 2017-18. Sr.no. - 25	Lowering down the debris obtained from breaking and removing the cement plaster / burnt brick masonry of the first floor by any means without causing dust nuisance and damage to structure, stacking the same as and where directed including cleaning the site complete. (Rate for loose material)	Cubic metre	463.59	486.77	4	1947.08
19	Add item for DSR 2017-18	Removing any kind of debris including loading in truck and conveying to dumping point approved by MCGM, unloading, spreading etc. complete. (SSR Transportation page no.362) (Note: rate to be reduced proportionally, if lead is within 50 km).	Cubic metre	583.275	612.44	4	2449.76

total 150663.49
add 12% G.ST 18079.62
add 0.5% labour cessRs 753.32
169496.42

Total amount = (One Lakh fifty thousand thousand six hundred and sixty three only)

Estimate prepared and checked by :

We quote _____ % i.e. _____ percentage (In words) above / Below / At Par
with estimated cost of Rs. 1,50663.00/-

Rubber Stamp of the firm
(Signature of the contractor)

University Engineer
(University of Mumbai)