



No.UEV /20/1004 of 2020

Mumbai – 400 032

Date:30/09/2020

TENDER NOTICE

Wax sealed tenders are invited by the University Engineer, University of Mumbai for the following work:

- 1 Name of work : Construction of Parking Road at KBP Boys Hostel, Vidyanagary Campus, University of Mumbai, Mumbai-98
- 2 Cost put to tender : Rs. 99,935/- without GST.
- 3 Cost of Tender form : Rs. 236/- (200 + GST) only
- 4 Last date for issuing of tender form : On 07/10/2020 before 1:00 PM
- 5 Last date for submission of tender form : On 07/10/2020 before 3:00 PM
- 6 Place and time for payment of tender form fees : University cash counter, Room no. 12, ground floor, cash unit, Fort Campus Building
- 7 Place and time of availability of 'Tender' : Office of University Engineer, Room No. 118, 1st floor, Fort Campus Building.
- 8 Place for submission of 'Tender' : Office of University Engineer, Room No. 118, 1st floor, Fort Campus Building.
- 9 Mode of payment of R.M.D. : R.M.D. will be 5% of work will be deducted in bill and return after defect liability period expired
- 10 Period within which work is to be done : 10 days after issue of work order
- 11 Defect liability period : 1 Year

The blank tender form (Schedule "B") must be submitted and details such as (i) Tender Fee Receipt No. & Date must invariably be written on it.

The contractor in the field should be PWD registered. Any over writing in tender document leads to rejection of tender.

Please note that, if any damages are done to electrical wiring, cabling etc. and internal, external pipeline during the repairing work shall be rectified / replaced by the contractor immediately at his own expense. The selected contractor will have to execute an agreement on Rs. 500/- Stamp paper. University of Mumbai will not be responsible for any postal delay/loss in transit

University Engineer, University of Mumbai reserves the right to reject all the tenders or any tender without assigning any reasons therefore and to relax or waive any of the condition stipulated in any of the tender that may be issued wherever necessary.

(S.V.Rane)

University Engineer
University of Mumbai.

SCHEDULE "B"

LAST DATE FOR SUBMISSION OF

TENDER FORM

No.UE/

/

of 2020

Challan No. _____ Date _____

M/s _____

Name of work : Construction of Parking Road at KBP Boys Hostel, Vidyanagary Campus, University of Mumbai, Mumbai-98

Sr. No.	Quantity	Description	Unit	Rate	Add 5% in rate for Corporation Area	Amount
1	15	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means As per PWD DSR 2019-20, Item No-21.02	Cubic Metre	157	164.85	2472.75
2	16	Providing dry/ trap/ granite/ quartzite/ gneiss rubble stone soling 15 cm to 20 cm thick including hand packing and compacting etc. complete. As per PWD DSR-2019-20, Item No-21.38, Page No- 210	Cubic Metre	1050	1102.5	17640
3	12	Providing and laying in situ /Ready Mix Cement concrete M-20 of trap / granite /quartzite/ gneiss metal for R.C.C. work in foundations like raft, strip foundations, grillage and footings of R.C.C. columns and steel stanchions etc. including bailing out water, Steel centering formwork, laying/pumping cover blocks, compaction and curing roughening the surface if special finish is to be provided (excluding reinforcement and structural steel) etc. complete, with fully automatic microprocessor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc)	Cubic Metre	5704	5989.2	71870.4
4	90	Providing and laying 125 micron Low Density Polyethylene (LDPE) sheet conforming to IS 3395:1997 below concrete pavement including all materials and labour complete. As per PWD DSR 2019-20, Item No-5.19, Page No- 60	Square Metre	20	21	1890
5	10	Removing any kind of debris including loading in truck and conveying to dumping point approved by MCGM, unloading, spreading etc. complete. (SSR Transportation page no.362) (Note: rate to be reduced proportionally, if lead is within 50 km). Add item for DSR 2017-18. Sr.no. - 20	Cubic metre	577.5	606.375	6063.75

Total Amount

99936.90

Say

99935.00

Add 12% GST

11,992.20


0.5% Labour Insurance

499.68


Total Amount I/c Tax

112,427.00

Total Amount = (Rs. Ninety Nine Thousand Nine Hundred Thirty Five Only)

Estimate Prepared & Checked by: 

We quote _____ % i.e. _____ percentage (In words) above / Below / At Par with estimated cost of Rs 99,935/-

Rubber Stamp of the firm
(Signature of the contractor)
University Engineer
(University of Mumbai)