

University of Mumbai

ESTIMATE

Name of the Work: Replacement of switchgears at main power supply in Meter Room, Ground Floor, Fort Campus.

Sr. No	. Description	Qty.	Rate	Unit	Amount
1)	Supplying & erecting triple pole and neutral distribution board(TPNDB) with door surface/ flush mounted suitable for 3 poleMCCB as incomer & outgoing SP MCB (36 poles) or TP MCBof 12 ways (36 poles)(CSR 5-4-27)	1	8,691.00	No.	8,691.00
2)	Providing & erecting 3 Pole MCCB of 200A,415V capacity withshort circuit rating 25 kA (CSR 5-5-2)	1	9,009.00	No.	9,009.00
3)	Supplying, erecting & marking FPMCB 63A 4 pole(CSR 5-3-17)	10	1,232.00	No.	12,320.00
4)	Supplying, erecting & marking DPMCB 40A 2 pole (CSR 5-3-8)	8	628.00	No.	5,024.00
5)	Supplying and erecting UPVC reinforced flexible conduit 50mm in dia.(CSR 1-2-5)	15	183.00	Mtr.	2,745.00
)	Supplying & erecting mains with 4x35 sq.mm F.R copper PVCinsulated wire(CSR 1-3-23)	24	1,280.00	Mtr.	30,720.00
1	Supplying & erecting Siemens type brass cable glands for 25 to 50 sq. mm.(CSR 7-7-4)	16	79.00	No.	1,264.00
	Supplying & erecting crimping type copper lugs for cable 25 sq.mm.(CSR 7-9-2)	16	23.00	No.	368.00
	Supplying &erecting mains with 2x10 sq.mm FRLSH copperPVC insulated wire (CSR 1-3-10)	12	192.00	Mtr.	2,304.00
1	Supplying & erecting CRCA sheet metal one way enclosures 4 way MS box (CSR 5-4-23)	1	339.00	No.	339.0
) S	Supplying and erecting metal work in CRCA sheet withfabrication of boxes, iron work(CSR 6-1-1)	25	226.00	Kgs.	5,650.0
) [Dismantling the existing switchgears	25	79.00	No.	1,975.0



University of Mumbai

	111111111111111111111111111111111111111	University of Mumbai					
	commissioning of maintenancefree earthing(CSR 9-1-5)	1	12,173.00	No.	12,173.00		
14)	Supplying and erecting GI strip 25 mm of required size used for earthing onwall(CSR 9-2-3)	50	191.00	Kgs.	9,550.00		
			Total Rs.		102,132.00		
		SGST @ 6%		6,128.00			
Rupe	es One lacFourteen Thousand three Hundred a	CGST @ 6%		6,128.00			
Eighty	y Eight Only	Grand Total Rs.		114,388.00			
				e w aller	A SHOW		

University Engineer University of Mumbai



No.UEV / 62/1016 of 2020 Mumbai - 400 032

TENDER NOTICE Date: 30/05/2020

the following work: Wax sealed tenders are invited by the University Engineer, University of Mumbai for

Name of work Replacement of Unserviceable Switchgears in Main Electrical Room, Fort, University of Mumbai.

Cost of Tender form Cost put to tender

date for issuing of tender form

0n_

|4||10|| 2020 before 11:00 AM

Rs. 224/- only

Rs 102132.00/- without GST

Last date of issuing and submission: On 2111 v 2020 before 3:00 PM

of tender form

form tees Place and time for payment of tender: University cash counter, Room no. 51, second floor, cash unit, Vidyanagari Campus Building.

Place and time of availability of:

Place for submission of 'Tender' Office of University Engineer, Room No. 118, 1st

floor, Fort Campus Building. floor, Fort Campus Building.

Office of University Engineer, Room No. 118, 1st

Period within which work is to be: 25days

Defect liability period 1 Year

Tender Fee Receipt No. & Date must invariably be written on it. The blank tender form (Schedule "B") must be submitted and details such as (i)

document leads to rejection of tender. The contractor in the field should be PWD registered. Any over writing in tender

contractor immediately at his own expense. Please note that, if any damages are done to electrical wiring, cabling etc. and internal, external pipeline during the repairing work shall be rectified / replaced by the

University of Mumbai will not be responsible for any postal delay/loss in transit. The selected contractor will have to execute an agreement on Rs 500/- stamp paper,

condition stipulated in any of the tender that may be issued wherever necessary. or any tender without assigning any reasons therefore and to relax or waive any of the University Engineer, University of Mumbai reserves the right to reject all the tenders

University of Mumbai University Engineer