



No.UEV /18/1658 of 2020
Mumbai – 400 032
Date: 08/12/2020

TENDER NOTICE

Wax sealed tenders are invited by the University Engineer, University of Mumbai for the following work:

- 1 Name of work : Repairing, Renovation & Painting work at Ground Floor Vasahat Room-02, Room-03 & Canteen at V.V.Bhavan "B" Road, Churchgate, Mumbai, Maharashtra 400020.
- 2 Cost put to tender : Rs. 2,60,600/-without GST
- 3 Cost of Tender form : Rs. 236/- (200 + GST) only
- 4 Last date for issuing of tender form : On 15/12/2020 before 1:00 PM
- 5 Last date for submission of tender form : On 15/12/2020 before 3:00 PM
- 6 Place and time for payment of tender form fees : University cash counter, Room no. 12, ground floor, cash unit, Fort Campus Building
- 7 Place and time of availability of 'Tender' : Office of University Engineer, Room No. 118, 1st floor, Fort Campus Building.
- 8 Place for submission of 'Tender' : Office of University Engineer, Room No. 118, 1st floor, Fort Campus Building.
- 9 Mode of payment of R.M.D. : R.M.D. will be 4% of work will be deducted in bill and return after defect liability period expired.
- 10 Period within which work is to be done : 15 days after issue of work order
- 11 Defect liability period : 1 Year

The blank tender form (Schedule "B") must be submitted and details such as (i) Tender Fee Receipt No. & Date must invariably be written on it.

The contractor in the field should be PWD registered.. Any over writing in tender document leads to rejection of tender.

Please note that, if any damages are done to electrical wiring, cabling etc. and internal, external pipeline during the repairing work shall be rectified / replaced by the contractor immediately at his own expense..

University Engineer, University of Mumbai reserves the right to reject all the tenders or any tender without assigning any reasons therefore and to relax or waive any of the condition stipulated in any of the tender that may be issued wherever necessary. The selected contractor will have to execute an agreement on Rs. 500/- Stamp paper. University of Mumbai will not be responsible for any postal delay/loss in transit.

(S.V.Rane)
University Engineer
University of Mumbai.



SCHEDULE 'B'

SCHEDULE "B"						
LAST DATE FOR SUBMISSION OF				No.UE/ / of 2020		
TENDER FORM				M/s		
Challan No. _____ Date _____						
Name of work : Repairing, Renovation & Painting work at Ground Floor Vasahat Room-02, Room-03 & Canteen at V.V.Bhavan "B" Road, Churchgate, Mumbai, Maharashtra 400020.						
Sr. No.	Quantity	Description	Unit	Rate	Add 5% in rate For Corporation Areas	Amount
1	8.00	Removing doors and windows with frames and stacking the materials as directed with all leads, lifts etc. complete. As per PWD DSR-2019-20, Item No-46.15, Page No- 387	Number	131.25	137.81	1102.50
2	4.00	Dismantling brick masonry in lime or cement mortar and stacking the materials as directed with all leads, lifts etc.	Cubic metre	281.4	295.47	1181.88
3	24.00	Removing cement tiles, or marble or polished shahabad floor or dado without bed concrete including stacking the materials as directed with all leads, lifts etc. complete. As per PWD DSR-2019-20, Item No-46.19, Page No- 387	Square Metre	37.8	39.69	952.56
4	1.08	Providing and fixing fiber glass reinforced polyester door shutter 35 mm thick as per IS 14856 (2000) (Reaffirmed 2006) without ventilator including chromium plated fixtures and fastening with chromium plated handles on both sides, etc complete. As per PWD DSR 2019-20, Item No-39.59.	Square Metre	2952.6	3100.23	3348.25
5	38.00	Providing internal cement plaster 20mm thick in two coats in cement mortar 1:4 without neeru finish, to concrete, brick surface, in all positions including scaffolding and curing etc.complete.As per PWD DSR-2019-20, Item No-32.07, Page No- 277	Square Metre	411.6	432.18	16422.84
6	24.00	Providing and laying vitrified mirror / glossy finish tiles having size 590 mm to 605 mm x 590 mm to 605 mm of 8 to 10 mm thickness and confirming to IS. 15622-2006 (group Bla) of approved make, shade and pattern for dado and skirting in required position fixed in 1:4 cement mortar including neat cement float, filling joints, curing and clearing etc. complete	Square Metre	1141.35	1198.42	28762.02
7	12.00	Providing and laying ceramic tiles having size 30 cm. x 60 cm. confirming to corresponding I.S. for dado and skirting in required position with readymade adhesive mortar of approved quality on plaster of 1:2 cement mortar including joint filling with white/ colour cement slurry cleaning curing etc. complete. As per PWD DSR-2019-20, Item No-33.27, Page No-286	Square Metre	1250.55	1313.08	15756.93

**SCHEDULE 'B'**

Sr. No.	Quantity	Description	Unit	Rate	Add 5% in rate For Corporation Areas	Amount
8	4.50	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:4 in half brick thick wall including mild steel longitudinal reinforcement of 2 bars of 6 mm diameter / 2 hoop iron strips 25 mm X 1.6 mm placed at every third course, properly bent and bonded at ends scaffolding, racking out joints and watering etc. complete. As per PWD DSR-2019-20, Item No-27.06, Page No- 263	Square Metre	855.75	898.54	4043.42
9	5.00	Providing second class Burnt Brick masonry with conventional / I.S. type bricks in cement mortar 1:4 including scaffolding, racking out joints and watering etc. in pillar of rectangular shapes as shown in the drawings or as directed complete. As per PWD DSR-2019-20, Item No-27.1, Page No- 263	Cubic Metre	6692.7	7027.34	35136.68
10	12.00	Providing and laying in trenches 20 mm dia. CPVC pipe including necessary excavation, fittings. Refilling trenches etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete. As per PWD DSR-2019-20, Item No-42.62, Page No- 368	Running Metre	256.2	269.01	3228.12
11	5.00	Providing and fixing on walls/ ceiling/ floors 20 mm dia. heavy grade having embossed as ISI Mark galvanised iron pipes of 1.93 kg/meter with necessary fitting remaking good the demolished portion and applying primer of anti-corrosive oil paint, 2 coats Including necessary scaffolding and removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete. As per PWD DSR-2019-20, Item No-41.11, Page No- 351	Running Metre	451.5	474.08	2370.38
12	1.00	Providing and fixing 15 mm dia. screw down bib/ stop tap of brass including necessary socket union nut complete. As per PWD DSR-2019-20, Item No-41.4, Page No- 354	Number	541.8	568.89	568.89
13	0.60	Providing sills of polished Kadappa stone 25mm to 30mm thick, on a bed of 1:4 cement mortar including cement float, filling joints with slurry, curing polishing and cleaning etc. complete. As per PWD DSR-2019-20, Item No-33.2, Page No- 285	Square Metre	987	1036.35	621.81
14	8.00	Providing and laying handcut polished Kotah Stone flooring 25mm to 30mm thick and 30cm wide in plain/diamond pattern on a bed of 1:6 C.M. including cement float, filling joints with neat cement slurry, curing, polishing and cleaning etc. complete. As per PWD DSR-2019-20, Item No-33.07, Page No- 282	Square Metre	1079.4	1133.37	9066.96



SCHEDULE 'B'

Sr. No.	Quantity	Description	Unit	Rate	Add 5% in rate For Corporation Areas	Amount
15	5.00	Providing and laying in position flooring of telephone black / Amba White / Cat bary brown / Ruby red / Ocean Brown granite stone of approved shade and size 18 mm to 20 mm thick on bed 1:6 cement mortar including cement floats striking joints, pointing in C.M. 1:3 curing and cleaning etc. complete. As per PWD DSR-2019-20, Item No-33.34, Page No- 287	Square Metre	3822	4013.10	20065.50
16	0.50	Providing and fabricating structural steel work in rolled sections like joists, channels, angles, tees etc. as per detailed design and drawings or as directed including cutting, fabricating, hoisting, erecting, fixing in position making riveted / bolted / welded connections without connecting plates, braces etc. and including one coat of anticorrosive paint and over it two coats of oil painting of approved quality and shade etc. complete. As per PWD DSR-2019-20, Item No-23.01, Page No- 232	Metric Tonne	77536.2	81413.01	40706.51
17	38	Providing internal cement plaster 20mm thick in two coats in cement mortar 1:4 without neeru finish, to concrete, brick surface, in all positions including scaffolding and curing etc. complete. As per PWD DSR-2019-20, Item No-32.07, Page No- 277	Square Metre	392	411.60	15640.80
18	160	Scrapping the old plastered internal surface with sand paper and coating the entire surface with mixture of whitening or glue and linseed oil including scaffolding etc. complete as directed. As per PWD DSR-2019-20, Item No-36.19, Page No- 325	Square Metre	28.7	30.14	4821.60
19	120	Providing and applying two coat of wall care putty on plastered surface and ceiling and walls to prepare surface even and smooth of approved make, etc. complete. As per PWD DSR-2019-20, Item No-32.34, Page No- 281	Square Metre	81	85.05	10206.00
20	160	Providing and applying priming coat on concrete/ masonry/ Asbestos Cement plastered surfaces including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required etc. complete. As per PWD DSR-2019-20, Item No-35.21, Page No- 297	Square Metre	30	31.50	5040.00
21	160	Providing and applying plastic emulsion paint of approved quality, colour and shade to old surface in three coats including scaffolding, preparing the surface. (excluding primer coat) etc. complete.	Square Metre	83.6	87.78	14044.80




SCHEDULE 'B'

Sr. No.	Quantity	Description	Unit	Rate	Add 5% in rate For Corporation Areas	Amount
22	5	Providing and fixing in position. (as per I.S.1868 / 1982) Aluminium sliding window of two tracks with rectangular pipe having overall dimension 63.50 x 38.10 x 1.02 mm at weight 0.547 kg/Rmt. and window frame bottom track section 61.85 x 31.75 x 1.20 mm at weight 0.695 kg/Rmt. Top and side track section 61.85 x 31.75 x 1.30 mm at weight 0.659 kg/Rmt. The shutter should be of bearing bottom 40 x 18 x 1.25 mm at weight 0.417 kg/Rmt. Inter locking section 40 x 18 x 1.10 mm at weight 0.469 kg/Rmt. And handle section 40 x 18 x 1.25 mm at weight 0.417 kg/Rmt. and top section 40 x 18 x 1.25 mm at weight 0.417 kg/Rmt. As per detailed drawings and as directed by Engineer in charge with all necessary Aluminium sections fixtures and fastenings such as roller bearing in nylon casting and self locking catch fitted in vertical section of shutter including 5 mm thick plain glass with all required screws and nuts etc, complete. With powder coating without box. As per PWD DSR 2019-20, Item No-39.4	Square Metre	4924	5170.20	25851.00
23	20.00	Providing and applying two coats of synthetic enamel paint of approved colour to new /old structural steel work and wood work in buildings, including scaffolding if necessary, cleaning and preparing the surface (excluding primer coat) etc. complete. As per PWD DSR-2019-20, Item No-35.07, Page No- 295	Square Metre	79	82.95	1659.00

Total Amount 260598.43
 Say 260600.00
 Add 12% GST 31,272.00
 0.5% Labour Insurance 1,303.00
 Total Amount I/c Tax 293,175.00


Total Amount = (Rs. Two Lakh Sixty Thousand Six Hundred Only)

Estimate Prepared by: 

Estimate Checked by: 

We quote _____ % i.e. _____ percentage (In words) above / Below / At Par
with estimated cost of Rs 2,60,600/-

Rubber Stamp of the firm
(Signature of the contractor)


University Engineer
(University of Mumbai)