



No. UEV/ 45/1710 of 2020

Mumbai – 400 098

Date: 11th Dec. 2020

TENDER NOTICE

Wax sealed tenders are invited by the University Engineer, University of Mumbai for the following work:

- | | | | |
|----|---|---|---|
| 1 | Name of work | : | Garden Infrastructure work at entrance of New Exam House building at Vidyanagari campus, University of Mumbai, Mumbai - 400 098. |
| 2 | Cost put to tender | : | Rs. 1,76,945.00/- (Excluding all the Taxes) (Rupees One Lakh Seventy Six Thousand Nine Hundred and Forty Five Only) (Excluding all the Taxes) |
| 3 | Cost of Tender form | : | Rs. 224/- (200 + 12% GST) only |
| 4 | Date for issuing of tender form | : | On 11 th 12/2020 after 11:00 AM |
| 5 | Last date for issuing and submission of tender form | : | On 18 th 12/2020 before 1:00 PM |
| 6 | Place and time for payment of tender form fees | : | University cash counter, Examination House, 2 nd floor, Room no-45 Vidyanagari Campus |
| 7 | Place and time of availability of 'Tender' | : | Office of University Engineer, Dr. Ambedkar Bhavan, 1 st floor, Vidyanagari Campus. |
| 8 | Place for submission of 'Tender' | : | Office of University Engineer, Dr. Ambedkar Bhavan, 1 st floor, Vidyanagari Campus. |
| 9 | Mode of payment of R.M.D. | : | R.M.D. will be 5% of work will be deducted in bill and return after defect liability period expired |
| 10 | Period within which work is to be done | : | 7 days after issue of work order |
| 11 | Defect liability period | : | 1 Year |


The blank tender form (Schedule "B") must be submitted and details such as (i) Tender Fee Receipt No. & Date must invariably be written on it.

The contractor in the field should be PWD registered. The rate should include all the taxes like GST. Any over writing in tender document leads to rejection of tender.

Please note that, if any damages are done to electrical wiring, cabling etc. and internal, external pipeline during the repairing work shall be rectified / replaced by the contractor immediately at his own expense.

The selected contractor will have to execute an agreement on Rs. 500/- Stamp paper. University of Mumbai will not be responsible for any postal delay/loss in transit.

University Engineer, University of Mumbai reserves the right to reject all the tenders or any tender without assigning any reasons therefore and to relax or waive any of the condition stipulated in any of the tender that may be issued wherever necessary.


University Engineer



Estimate

Name of work : Garden infrastructure work at entrance of New Exam House Building at Vidyanagari Campus, University of Mumbai, Mumbai-98

Sr. No.	Item No.	Description	Unit	Rate	Add 5% in rate For Corporat ion Areas	Quantity	Amount
1	21.02	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means	Cubic Metre	157	164.85	10.25	1689.71
2	24.06	Providing and laying Cast in situ/Ready Mix cement concrete in M20 of trap/ granite/quartzite/gneiss metal for steps including steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface, only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc)	Cubic Metre	5456	5728.8	20.5	117440.4
3	27.05	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete	Cubic Metre	6004	6304.2	1.37	8636.75
4	32.11	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 kg per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete.	Square Metre	679	712.95	8.5	6060.08
5	33.37	Providing and fixing machine cut mirror polished 18 mm to 20 mm thick telephone black / Amba White / Cat bary brown / RBI red / Ocean Brown granite stone partition with full moulding the edges etc. complete. One side polish	Square Metre	3629	3810.45	5.65	21529.04

University of Mumbai



Sr. No.	Item No.	Description	Unit	Rate	Add 5% in rate For Corporat ion Areas	Quantity	Amount
6	35.21	Providing and applying priming coat on concrete/ masonry/ Asbestos Cement plastered surfaces including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required etc. complete.	Square Metre	30	31.5	33.65	1059.98
7	35.26	Providing and applying two coats of exterior weather shield paint of approved manufacture and of approved colour to the plastered surfaces including cleaning ,preparing the plaster surface ,applying primer coat ,scaffolding if necessary, and watering the surface for two days etc complete. NOTE: For Item No. 15 to 18 prior approval of Superintending Engineer will be necessary	Square Metre	213	223.65	33.65	7525.82
8	Point No. 20, Page No. 529 of SSR 2019-20	Aggregate 10 mm	Cubic Metre	800	-	11	8800
9	Page No. 532 of SSR 2019-20	Skilled Labour for spreading aggregate on pathway	Nos.	539	-	4	2156
10	Page No. 532 of SSR 2019-20	Helper Un Skilled for spreading aggregate on pathway	Nos.	512	-	4	2048
Total							176,945.8
Say Total							1,76,945/-
12% GST							21,233.5
0.5% Labour Insurance							884.7
Total incl. Taxes							199,064.0

Total Amount = (Rs. One Lakh Seventy Six Thousand Nine Hundred Forty Five only)

Estimate Prepared & Checked by:

University Engineer
(University of Mumbai)