

University of Mumbai

पायाभूत सुविधा नियोजन,
अंमलबजावणी व देखभाल विभाग,
मुंबई विद्यापीठ,
मुख्य इमारत, खोली क्रमांक ११८,
पहिला मजला, महात्मा गांधी रोड,
फोर्ट, मुंबई, महाराष्ट्र - ४०० ०३२
ई-मेल : cdu@mu.ac.in



IPEMD/ 2022-23

Infrastructure Planning, Execution
and Maintenance department,
University of Mumbai,
Main Building, R. No. 118, 1st floor,
Mahatma Gandhi Road, Fort,
Mumbai, Maharashtra - 400 032
E-mail : cdu@mu.ac.in
Tel : 022-68320020, 022-22677667

Ref. No.- CDU/01-COVID/293 of 2022-23

Date : 06/05/2022

TENDER NOTICE


Wax sealed tenders are invited by the University Engineer, University of Mumbai for following work :

- 1 Name of work : Providing false ceiling and door in R no. 109, Dean Si-Tech, 1st floor, Fort Campus, University of Mumbai
- 2 Cost put to tender : Rs. 1,09,109/- (Rupees One Lakh Nine Thousand One Hundred and Nine Only) excluding all the taxes
- 3 Cost of Tender form : Rs. 224/- (200 + 12% GST)
- 4 Date for issuing of tender form : 07/05/2022 after 11:00 AM
- 5 Last date for issuing and submission of tender form : 14/05/2022 before 01:00 PM
- 6 Place and time for payment of tender form fees : University cash counter, Fort Campus
- 7 Place and time of availability of 'Tender' : Office of University Engineer, Fort Campus.
- 8 Place for submission of 'Tender' : Office of University Engineer, Fort Campus.
- 9 Period within which work is to be done : 07 days after issue of work order

The blank tender form (Schedule "B") must be submitted and details such as (i) Tender Fee Receipt No. & Date must invariably be written on it.

The contractor in the field should be PWD registered. The rate should be exclusive of all the taxes. Any over writing in tender document leads to rejection of tender. Please note that, if any damages are done to electrical wiring, cabling etc. and internal, external pipeline during the repairing work shall be rectified / replaced by the contractor immediately at his own expense. University of Mumbai will not be responsible for any postal delay/loss in transit.

University Engineer reserves the right to reject all the tenders or any tender without assigning any reasons therefore and to relax or waive any of the condition stipulated in any of the tender that may be issued wherever necessary.


(S. V. Rane)
University Engineer
IPEMD, Fort/Kalina
University of Mumbai

(E)



Estimate

me of work : Providing and fixing False ceiling and Door in room no.109 on 1st floor. University of Mumbai, Fort Campus, Mumbai-32.

Sr. No.	SSR Item No.	Quantity	Description	Unit	Rate	5%	Amount
1	43.13	48	Providing and laying in trenches 40 mm dia. heavy grade having embossed as ISI Mark galvanised iron pipes of 4.49 Kilogram/metre necessary fitting remaking good the demolished portion with filling trenches and with primer of anti-corrosive oil paint, 2 coats complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	Running Metre	687	721.35	34624.80
2	38.51	32	Providing and fixing in position Gypsum board false ceiling with 12.5 mm thick Gypsum boards, screwed/fixed to the under structure of suspended G.I. Grid constructed and suspended from the main ceiling consisting of ceiling sections of size 25 x 50 mm maximum center to center distance of 600 millimetre perimeter channel and intermediate channels at maximum center to center distance 1200 millimetre galvanized grid should be fixed to reinforced cement concrete slab. The gypsum board should be fixed to galvanized iron grid with necessary screws. The boards should be taped and filled from underside to give smooth, seamless ceiling. The rate should include necessary additional ceiling sections and intermediate channels. Additional intermediate channels should be fixed to strap hangers for additional support to prevent strapping at every 1200 millimetre item to be completed in all respect including necessary sleeves for ducts finishing of joints cut outs, painting including labour, material, lifts etc. all complete.	Square Metre	1637	1718.85	55003.20
3	46.15	1	Removing doors and windows with frames and stacking the materials as directed with all leads, lifts etc. complete	Number	147	154.35	154.35
4	Additional Item	1.95	Providing and fixing on site full ht.both side matching venner door shutters ar required location and having height more than 1.5meter made by using soild core commercial type flush door 35mm thick of the requisite manufacture viz Anchor/Century/kenwood/duro or equivalent generally confirming to I.S.303/I.S. 710-1980 finished with 3.5 to 4mm thick matching veneer finished with grooves on both sides including melamine polishing. Antitermite treatment to plywood and woodwork with ten year guarantee bond etc including leads and lifts etc complete. Necessary lipping(BTC), moulding, brass fixtures, fastening, door closer, door stopper, hinges, handles, tower bolts, mortise lock etc with malemine polish etc. complete	Square Metre	9242	9242	18021.90
6	SSR 2019-20 pg no. 524	1	Providing and fixing Hydraulic door closer as per detailed design and drawings or as directed by engineer in charge including all materials, labours, and equipment etc. complete.Note: In SSR only material rate was givenRs. 1130/unit of door closer, 10% is added for installation	Number	1305	1305	1305.00
Total Amount							1,09,109.25
Add 12% GST							13,093.11
Total Amount I/c Tax							1,22,202.36

Estimate Prepared & Checked by:

[Signature]

We quote — % i.e. — percentage
(in words) above/below/at par than estimated
cost of Rs. 109109/—.

[Signature]
University Engineer
(University of Mumbai)

(Rubber stamp & signature of contractor)