



No.UE / 14 /559 of 2020

Mumbai - 400 032

Date:18/08/2020

TENDER NOTICE

Wax sealed tenders are invited by the University Engineer, University of Mumbai for the following work:

- 1 Name of work : Providing and constructing Brick Masonry Inspection Chamber at J.S. Hostel, "B" Road, Churchgate, Mumbai, Maharashtra 400020
- 2 Cost put to tender : Rs. 1,50,465 /- without GST.
- 3 Cost of Tender form : Rs. 236/- (200 + GST) only
- 4 Last date for issuing of tender form : On ~~25~~25/08/2020 before 1:00 PM
- 5 Last date for submission of tender form : On ~~25~~25/08/ 2020 before 3:00 PM
- 6 Place and time for payment of tender form fees : University cash counter, Room no. 12, ground floor, cash unit, Fort Campus Building
- 7 Place and time of availability of 'Tender' : Office of University Engineer, Room No. 118, 1st floor, Fort Campus Building.
- 8 Place for submission of 'Tender' : Office of University Engineer, Room No. 118, 1st floor, Fort Campus Building.
- 9 Mode of payment of R.M.D. : R.M.D. will be 5% of work will be deducted in bill and return after defect liability period expired
- 10 Period within which work is to be done : 15 days after issue of work order
- 11 Defect liability period : 1 Year

The blank tender form (Schedule "B") must be submitted and details such as (i) Tender Fee Receipt No. & Date must invariably be written on it.

The contractor in the field should be PWD registered. Any over writing in tender document leads to rejection of tender.

Please note that, if any damages are done to electrical wiring, cabling etc. and internal, external pipeline during the repairing work shall be rectified / replaced by the contractor immediately at his own expense.

University Engineer, University of Mumbai reserves the right to reject all the tenders or any tender without assigning any reasons therefore and to relax or waive any of the condition stipulated in any of the tender that may be issued wherever necessary.


(S.V.Rane)

University Engineer

SCHEDULE "B"

LAST DATE FOR SUBMISSION OF
TENDER FORM

No. I F / _____ of 2020
M/s _____


Challan No. _____ Date _____

Name of work Providing and constructing Brick Masonry Inspection Chamber at J.S. Hostel, "B" Road, Churchgate Mumbai, Maharashtra 400020

Sr. No.	Quantity	Description	Unit	Rate	Add 5% in rate for Corporation Area	Amount
1	8	Excavation for foundation in earth, soils of all types, sand, gravel and soft murum, including removing the excavated material upto a distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete (Lift from 1.5m to 3.0m) By Mechanical Means As per PWD DSR 2019-20, Item No-21.04, Page no-206	Cubic Metre	196	205.8	1646.4
2	15	Providing and constructing Brick Masonry Inspection Chamber 60cm x 45cm x 90cm including 1:4:8 cement concrete foundation 1:2:4 cement concrete channels half round G.S.W. pipes, Brick Masonry, plastering from inside and with frame fixed in cement concrete with R.C.C. Cover medium duty 140 kg with frame etc complete. As per PWD DSR 2019-20, Item No-42.12, Page no-361	Number	6975	7323.75	109856.25
3	2	Providing and constructing Ductile Iron circular manhole 45 cm dia. At top 90 cm at bottom up to 1.80 meter to 2.70 meter depth including excavation, laying 1:4:8 cement concrete bedding 15 cm thick burnt brick masonry with 1:1 cement mortar plaster 25 mm thick inside and outside 20 mm (1:3) ductile iron heavy type cover with ring 125 kg in weight. High strength. More life and Durability, Good Antiskid Grip, Suitable to heavy theatric loading, Light weight casting after cost benefits for Transportation Refilling etc. as per requirement. with prior approval of concerned Superintending Engineer. As per PWD DSR 2019-20, Item No-50.31, Page no-444	No.	12000	12600	25200
4	80	Manually clearing the chokes from under ground drainage line including inspection chambers with the help of required tools for prope functioning line chamber to chamber etc. complete. As per PWD DSR-2019-20, Item No-46.54, Page No- 392	Running Metre	39	40.95	1276
5	2	Removing any kind of debris including loading in truck and conveying day to day basis to approved dumping point etc complete with all lifts and lead of 52 Km (As directed by Engineer in Charge) As per PWD DSR 2015-2016, Page No-195	One Trip	4994	5243.7	10487.4

Total Amount	150466.05
Say	150465.00
Add 12% GST	18,055.80
0.5% Labour Insurance	752.33
Total Amount I/c Tax	169,274.00

Total Amount = (Rs. One Lakh Fifty Thousand Four Hundred Sixty Five Only)

Estimate Prepared by: 

Estimate Checked by: _____

We quote _____ % i.e. _____ percentage (In words) above / Below / At Par with estimated cost of Rs. 1,50,465 /-

Rubber Stamp of the firm
(Signature of the contractor)


University Engineer
(University of Mumbai)