



No.UEV/ /499 of 2020

Mumbai – 400 098

Date: 10/08/2020

**TENDER NOTICE**

Wax sealed tenders are invited by the University Engineer, University of Mumbai for the following work:

- 1 Name of work : External Repairing and painting and P.C.C. work at Dr. Pandita Ramabai Girls Hostel building at Vidyanagari campus, University of Mumbai, Mumbai - 400 098.
- 2 Cost put to tender : Rs. 2,66,588/- (Excluding all the Taxes) (Rupees Two Lakhs Sixty Six Thousand Five Hundred and Eighty Eight Only Only) (Excluding all the Taxes)
- 3 Cost of Tender form : Rs. 224/- (200 + 12% GST) only
- 4 Date for issuing of tender form : On 11/08/2020 after 11:00 AM
- 5 Last date for issuing and submission of tender form : On 13/08/2020 before 1:00 PM
- 6 Place and time for payment of tender form fees : University cash counter, Examination House, 2<sup>nd</sup> floor, Room no-45 Vidyanagari Campus
- 7 Place and time of availability of 'Tender' : Office of University Engineer, Dr. Ambedkar Bhavan, 1<sup>st</sup> floor, Vidyanagari Campus.
- 8 Place for submission of 'Tender' : Office of University Engineer, Dr. Ambedkar Bhavan, 1<sup>st</sup> floor, Vidyanagari Campus.
- 9 Mode of payment of R.M.D. : R.M.D. will be 5% of work will be deducted in bill and return after defect liability period expired
- 10 Period within which work is to be done : 1 Month after issue of work order
- 11 Defect liability period : 1 Year


The blank tender form (Schedule "B") must be submitted and details such as (i) Tender Fee Receipt No. & Date must invariably be written on it.

The contractor in the field should be PWD registered. The rate should include all the taxes like GST. Any over writing in tender document leads to rejection of tender.

Please note that, if any damages are done to electrical wiring, cabling etc. and internal, external pipeline during the repairing work shall be rectified / replaced by the contractor immediately at his own expense.

The selected contractor will have to execute an agreement on Rs. 100/- Stamp paper. University of Mumbai will not be responsible for any postal delay/loss in transit.

University Engineer, University of Mumbai reserves the right to reject all the tenders or any tender without assigning any reasons therefore and to relax or waive any of the condition stipulated in any of the tender that may be issued wherever necessary.

  
University Engineer



**SCHEDULE 'B'**

LAST DATE FOR SUBMISSION OF  
TENDER FORM \_\_\_\_\_

No. UEV/ / \_\_\_\_\_  
M/s. \_\_\_\_\_ of 2020

Challan No. \_\_\_\_\_ Date: \_\_\_\_\_

Name of work : External Repairing and painting and P.C.C. work at Pandita Ramabai Girls Hostel building at Vidyanageri campus, University of Mumbai, Mumbai - 400 098.							
Sr. No.	Item No.	Description	Unit	Rate	Add 5% in rate for Corporation Area	Quantity	Amount
1	21.02	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting	Cubic Metre	157	164.85	8	1318.80
2	Add item for DSR 2017-18. Sr.no. - 20	Removing any kind of debris including loading in truck and conveying to dumping point approved by MCGM, unloading, spreading etc. complete. (SSR Transportation page no.362) (Note: rate to be reduced proportionally, if lead is within 50 km).	Cubic metre	577.5	606.38	8	4851.00
3	21.38	Providing dry/ trap/ granite/ quartzite/ gneiss rubble stone soling 15 cm to 20 cm thick including hand packing and compacting etc. complete.	Cubic Metre	1050	1102.50	6	6615.00
4	24.06	Providing and laying Cast in situ/Ready Mixcement concrete in M20 of trap/ granite/quartzite/gneiss metal for steps including steel centering, plywood/steel formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface, only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With natural sand/V.S.I. quality Artificial Sand	Cubic Metre	5456	5728.80	6	34372.80
5	32.11	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 kg per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete.	Square Metre	679	712.95	48	34221.60

6	Additional item for DSR 2017-18. Sr.no. - 5	Providing and applying Anticorrosive treatment to exposed reinforcement portion for Beam/Column with one coat of alkaline RUST Converter feouert/Rusticide or equivalent on exposed reinforcement after cleaning the surface with wire brush, followed by two coats of anticorrosive epoxy based two component zinc richprimer MasterEmaco P 130 of BASF phenolic IPNET RB/POLYALK FLXOPRIME or equivalent rebar protection coating on exposed reinforcement and concrete penetratingcorrosion inhibitor EPCO KP-/POLYALK EP 113/ Master Seal 1414 of BASF/FOSROC or equivalent over adjoining concrete surfaced.( Excluding all taxes) (As directed by Superintending	Square Metre	282	296.10	25	7402.50
7	Additional item for DSR 2017-18. Sr.no. - 6	Providing and applying of bond coat approved epoxy resin MasterBrace 1414 of BASF / EPI Bond of Krishna Conchem/ or equivalent before polymer plaster/concrete to have the perfect bond between old concrete and new concrete /polymer plaster surface within half an hour of after application of bond coat conforming to ASTM C 881 Type 2, using nylon brushes scaffolding labour etc. complete. ( Excluding all Taxes) (As directed by Superintending Engineer in Charge)	Square Metre	309	324.45	25	8111.25
8	Additional item for DSR 2017-18. Sr.no. - 8a	Providing and applying 30mm thick polymer mortar to load carrying R.C.C. members in two layers in propotion of 1.5:15 by weight of high dispersion polymer having solid content 37%+. 1% MasterEmaco SBR 2 of BASF/FOSROC/Krishna Conchem or equivalent approved make and quality, cement and Quartz sand with required water cement ratio for desired consistency and applying and finishing by floating,curing after initial setting time applying bonding coat for 2nd coat etc. as per manufactures specification etc. complete ( Excluding all taxes) (As directed by Superintending Engineer in Charge)	Square Metre	926	972.30	40	38892.00
9	35.21	Providing and applying priming coat on concrete/ masonry/ Asbestos Cement plastered surfaces including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required etc. complete.	Square Metre	30	31.50	500	15750.00
10	35.26	Providing and applying two coats of exterior weather shield paint of approved manufacture and of approved colour to the plastered surfaces including cleaning ,preparing the plaster surface ,applying primer coat ,scaffolding if necessary, and watering the surface for two days etc complete. NOTE: For item No. 15 to 18 prior approval of Superintending Engineer will be necessary	Square Metre	213	223.65	500	111825.00
11	35.19	Providing and applying priming coat over new wood and wood based surfaces, including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter, sand papering and knotting, scaffolding etc. complete.	Square Metre	27	28.35	29	822.15

12	35.07	Providing and applying two coats of synthetic enamel paint of approved colour to new /old structural steel work and wood work in buildings, including scaffolding if necessary, cleaning and preparing the surface (excluding primer coat) etc. complete.	Square Metre	79	82.95	29	2405.55	
							<b>Total Rs</b>	266587.65
							<b>Say Rs</b>	266,588.00
							<b>Add 12% GST</b>	31,990.56
							<b>Add 0.5% labour cess</b>	1,332.94
							<b>Total</b>	299,911.50


**Total Amount = ( Rupees Two Lakhs Sixty Six Thousand Five Hundred and Eighty Eight Only) (Excluding all the Taxes)**

Estimate Prepared and checked by:



We quote \_\_\_\_\_% i.e. \_\_\_\_\_ percentage (In words) above / Below / At Par with estimated cost of Rs. 2,66,588.00/- (Excluding all the Taxes)

Rubber Stamp of the firm  
(Signature of the contractor)



University Engineer  
(University of Mumbai)