



No.UEV /18/1659 of 2020
Mumbai – 400 032
Date: 08/12/2020

TENDER NOTICE

Wax sealed tenders are invited by the University Engineer, University of Mumbai for the following work:

- 1 Name of work : Replacing Entry Gates, side gate & fencing work at Sport Pavilion, University of Mumbai, Marine Drive, Churchgate, Mumbai, Maharashtra 400020.
- 2 Cost put to tender : Rs. 1,97,355/-without GST
- 3 Cost of Tender form : Rs. 236/- (200 + GST) only
- 4 Last date for issuing of tender form : On 15/12/2020 before 1:00 PM
- 5 Last date for submission of tender form : On 15/12/2020 before 3:00 PM
- 6 Place and time for payment of tender form fees : University cash counter, Room no. 12, ground floor, cash unit, Fort Campus Building
- 7 Place and time of availability of 'Tender' : Office of University Engineer, Room No. 118, 1st floor, Fort Campus Building.
- 8 Place for submission of 'Tender' : Office of University Engineer, Room No. 118, 1st floor, Fort Campus Building.
- 9 Mode of payment of R.M.D. : R.M.D. will be 4% of work will be deducted in bill and return after defect liability period expired.
- 10 Period within which work is to be done : 15 days after issue of work order
- 11 Defect liability period : 1 Year

The blank tender form (Schedule "B") must be submitted and details such as (i) Tender Fee Receipt No. & Date must invariably be written on it.

The contractor in the field should be PWD registered.. Any over writing in tender document leads to rejection of tender.

Please note that, if any damages are done to electrical wiring, cabling etc. and internal, external pipeline during the repairing work shall be rectified / replaced by the contractor immediately at his own expense..

University Engineer, University of Mumbai reserves the right to reject all the tenders or any tender without assigning any reasons therefore and to relax or waive any of the condition stipulated in any of the tender that may be issued wherever necessary. The selected contractor will have to execute an agreement on Rs. 500/- Stamp paper. University of Mumbai will not be responsible for any postal delay/loss in transit.

(S.V.Rane)
University Engineer
University of Mumbai.

SCHEDULE "B"						
LAST DATE FOR SUBMISSION OF TENDER FORM				No.UE/ / of 2020		
Challan No.		Date		M/a		
Name of work : Replacing Entry Gates, side gate & fencing work at Sport Pavilion, University of Mumbai, Marine Drive, Churchgate, Mumbai, Maharashtra 400020.						
Sr. No.	Quantity	Description	Unit	Rate	Add 5% In rate for Corporation Area	Amount
1	24	Removing iron pipe railing having wooden R.C.C. or C.C. or iron post and stacking the materials as directed etc. complete. As per PWD DSR 2020-21, Item No-23.01	Running Metre	63	66.15	1587.60
2	1.35	Providing and fabricating structural steel work in rolled sections like joists, channels, angles, tees etc. as per detailed design and drawings or as directed including cutting, fabricating, hoisting, erecting, fixing in position making riveted / bolted /welded connections without connecting plates, braces etc. and including one coat of anticorrosive paint and over it two coats of oil painting of approved quality and shade etc. complete. As per PWD DSR 2020-21, Item No-23.01	Metric Tonne	75938	79734.9	107642.12
3	35	Providing & applying structural grade epoxy latex bond coat prior to application of any type of mortar conforming to IS codes or equivalent to ensure bond between old concrete & new concrete by brush application etc complete. As per PWD DSR 2019-20, Item No-19.33	Square Meter	765	803.25	28113.75
4	35	Providing & applying 2 coats of compatible Polyurethane on epoxy fiber wrapped surface with brush /spray application etc complete. As per PWD DSR 2019, Item No 19.34	Square Meter	796	835.8	29253.00
5	15	Providing and erecting chain link fencing 1.6 M. height with G.I. chain link of size 50 x 50 mm, 8 gauge thick and fixed 75 mm above ground level on vertical M.S. Angles of 40 x 40 x 6 mm size, including excavating pits for foundation and embedded in C.C. block of 1:4:8 mix of size 450 x 450 x 670 mm. at 1.75 M. c/c with iron bar 16mm dia as hold fast including welding link with angle frame at 30 cm c/c with nuts and bolts and horizontal M.S. Angles at top and bottom of 25 x 25 x 5 mm size and vertical M.S. flat 35 x 5 mm and 25 x 5 mm horizontal including cross support of 40 x 40 x 6 mm angles both side at every corner or bend embedded in concrete blocks of 1:4:8 of size 450 x 450 x 670 mm including 3 coats of oil painting etc. complete. As per PWD DSR 2020-21, Item No-46.39	Running Metre	1953	2050.65	30759.75
Total Amount						197356.22
Say						197355.00
Add 12% GST						23,682.60
Total Amount						221,038.00

Total Amount = (Rs. One Lakh Ninety Seven Thousand Three Hundred Fifty Five Only)

Estimate Prepared by: 

Estimate Checked by: 

We quote _____ % i.e. _____ percentage (In words) above / Below / At Par
with estimated cost of Rs 1,97,355/-

Rubber Stamp of the firm
(Signature of the contractor)


University Engineer
(University of Mumbai)