

University of Mumbai

पायाभूत सुविधा नियोजन,
अंमलबजावणी व देखभाल विभाग,
मुंबई विद्यापीठ,
मुख्य इमारत, खोली क्रमांक ११८,
पहिला मजला, महात्मा गांधी रोड,
फोर्ट, मुंबई, महाराष्ट्र - ४०० ०३२
ई-मेल : cdu@mu.ac.in



IPEMD/ 2021-22

Infrastructure Planning,
Execution and Maintenance
department,
University of Mumbai,
Main Building, R. No. 118, 1st
floor, Mahatma Gandhi Road, Fort,
Mumbai, Maharashtra - 400 032
E-mail : cdu@mu.ac.in
Tel : 022-68320020, 022-22677667

Ref. No.- CDU/01-COVID/797 of 2021-22

Date : 03/08/2021

TENDER NOTICE

Wax sealed tenders are invited by the University Engineer, University of Mumbai for following work :

- | | | | |
|---|---|---|--|
| 1 | Name of work | : | Repairing and painting of room no. 204 and 205 on 2 nd floor, Fort campus, University of Mumbai |
| 2 | Cost put to tender | : | Rs. 1,54,187/- (Rupees One Lakh Fifty Four Thousand One Hundred Eighty Seven Only) excluding all the taxes |
| 3 | Cost of Tender form | : | Rs. 224/- (200 + 12% GST) |
| 4 | Date for issuing of tender form | : | 04/08/2021 after 11:00 AM |
| 5 | Last date for issuing and submission of tender form | : | 11/08/2021 before 01:00 PM |
| 6 | Place and time for payment of tender form fees | : | University cash counter, Fort Campus |
| 7 | Place and time of availability of 'Tender' | : | Office of University Engineer, Fort Campus. |
| 8 | Place for submission of 'Tender' | : | Office of University Engineer, Fort Campus. |
| 9 | Period within which work is to be done | : | 10 days after issue of work order |

The blank tender form (Schedule "B") must be submitted and details such as (i) Tender Fee Receipt No. & Date must invariably be written on it.

The contractor in the field should be PWD registered. The rate should be exclusive of all the taxes. Any over writing in tender document leads to rejection of tender. Please note that, if any damages are done to electrical wiring, cabling etc. and internal, external pipeline during the repairing work shall be rectified / replaced by the contractor immediately at his own expense. University of Mumbai will not be responsible for any postal delay/loss in transit. University Engineer reserves the right to reject all the tenders or any tender without assigning any reasons therefore and to relax or waive any of the condition stipulated in any of the tender that may be issued wherever necessary.

(S. V. Rane)
University Engineer
IPEMD, Fort
University of Mumbai



UNIVERSITY OF MUMBAI
ESTIMATE

Name of work : Repairs and painting to room no.204 & 205 on 2nd floor at Fort Campus, University of Mumbai, Mum-32

Qty.	Description of Item	Rate	Unit Per	Amount
40.00 Square Metres	1. Removing the existing cement plaster of any thickness without causing dust nuisance and stacking the debris upto a distance of 50 metres or spreading in the compound and cleaning the site etc. complete.			
	(SSR 2020-21/32.33)	47.00		
	Add 5% For Corpn.	2.35		
	Total	49.35	Sqm.	1974.00
12.00 Numbers	2. Removing doors and windows with frames and stacking the materials as directed with all leads, lifts etc. complete.			
	(SSR 2020-21/46.15)	142.00		
	Add 5% For Corpn.	7.10		
	Total	149.10	No.	1789.20
40.00 Square Metres	3. Scrapping the old plastered internal surface with sand paper and coating the entire surface with mixture of whitening or glue and linseed oil including scaffolding etc. complete as directed.			
	(SSR 2020-21/36.19)	33.00		
	Add 5% For Corpn.	1.65		
	Total	34.65	Sqm.	1386.00
250.00 Square Metres	4. Providing and applying priming coat on concrete/ masonry/ Asbestos Cement plastered surfaces including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required etc. complete.			
	(SSR 2020-21/35.21)	34.00		
	Add 5% For Corpn.	1.70		
	Total	35.70	Sqm.	8925.00
250.00 Square Metres	5. Providing and applying plastic emulsion paint of approved quality, colour and shade to old surface in three coats including scaffolding, preparing the surface. (excluding primer coat) etc. complete.			
	(SSR 2020-21/36.13)	87.00		
	Add 5% For Corpn.	4.35		
	Total	91.35	Sqm.	22837.50



Qty.	Description of Item	Rate	Unit Per	Amount
250.00 Square Metres	6. Providing and applying French polish for required finish on previously polished wood including knotting, preparing the surfaces, scaffolding etc. complete as directed (SSR 2020-21/34.05) 114.00 Add 5% For Corpn. 5.70 <hr/> Total 119.70	119.70	Sqm.	29925.00
7.00 Square Metres	7. Providing and fixing in position Colour anodized aluminium openable window of any size as per detailed drawing and as directed by Engineer incharge with all necessary alluminium sections including necessary fixtures and fastening with 5 mm thick clear float glass etc. complete. (SSR 2020-21/39.51(a)) 5663.00 Add 5% For Corpn. 283.15 <hr/> Total 5946.15	5946.15	Sqm.	41623.05
6.00 Square Metres	8. Providing and fixing in position aluminium fixed window fully glazed of any size as per detailed drawing and as directed by Engineer incharge with all necessary alluminium sections including necessary fixtures and fastening such as 5 mm thick clear float glass etc. complete. a) Without powder coating. Note While arriving at the rate of item of item weight at 6.90 kg/Sqm is considered. (SSR 2020-21/39.52) 4532.00 Add 5% For Corpn. 226.60 <hr/> Total 4758.60	4758.60	Sqm.	28551.60
4.00 Square Metres	9. Providing and fixing in position powder coated aluminium louvered windows / ventilator of various sizes with powder coating as per detailed drawing and specifications including aluminium frames 80 x 38 mm x 1.22 mm box type, 5 mm thick sheet glass louvers, of approved quality etc. complete. (SSR 2020-21/39.68) 2841.00 Add 5% For Corpn. 142.05 <hr/> Total 2983.05	2983.05	Sqm.	11932.20



Qty.
1.00
trip

Description of Item	Rate	Unit Per	Amount
10. Removing any kind of debris including loading in truck and conveying day to day basis to approved dumping point i.e. @ urban / industry loading sreading etc. complete with all leads and lifts (lead 52 km)			

MuCir DSR 15-16 P-195/I-37

2.00

Add 5% For Corpn. 249.70

Total	5243.70	5243.70	Smt.	5243.70
-------	---------	---------	------	---------


Total (A) Work Portion Rs. : 154187.25

Total (A = 154187.25) = Rs. : 154187.25

ADD 12% GST Rs. 18502.47

Total Rs. 172689.72

Say Rs. : 172690.00


Junior Engineer


University Engineer