

University of Mumbai

पायाभूत सुविधा नियोजन,
अंमलबजावणी व देखभाल विभाग,
मुंबई विद्यापीठ,
मुख्य इमारत, खोली क्रमांक ११८,
पहिला मजला, महात्मा गांधी रोड,
फोर्ट, मुंबई, महाराष्ट्र - ४०० ०३२
ई-मेल : cdu@mu.ac.in



IPEMD/ 2022-23

Infrastructure Planning, Execution
and Maintenance department,
University of Mumbai,
Main Building, R. No. 118, 1st floor,
Mahatma Gandhi Road, Fort,
Mumbai, Maharashtra - 400 032
E-mail : cdu@mu.ac.in
Tel : 022-68320020, 022-22677667

Ref. No.- CDU/01-COVID/202 of 2022-23

Date : 27/04/2022

TENDER NOTICE


Wax sealed tenders are invited by the University Engineer, University of Mumbai for following work :

- 1 Name of work : Repairs and painting in room no. 138 on 1st floor, Main Building of Fort Campus, University of Mumbai
- 2 Cost put to tender : Rs. 1,82,854/- (Rupees One Lakh Eighty Two Thousand Eight Hundred Fifty Four Only) excluding all the taxes
- 3 Cost of Tender form : Rs. 224/- (200 + 12% GST)
- 4 Date for issuing of tender form : 28/04/2022 after 11:00 AM
- 5 Last date for issuing and submission of tender form : 05/05/2022 before 01:00 PM
- 6 Place and time for payment of tender form fees : University cash counter, Fort Campus
- 7 Place and time of availability of 'Tender' : Office of University Engineer, Fort Campus.
- 8 Place for submission of 'Tender' : Office of University Engineer, Fort Campus.
- 9 Period within which work is to be done : 15 days after issue of work order

The blank tender form (Schedule "B") must be submitted and details such as (i) Tender Fee Receipt No. & Date must invariably be written on it.

The contractor in the field should be PWD registered. The rate should be exclusive of all the taxes. Any over writing in tender document leads to rejection of tender. Please note that, if any damages are done to electrical wiring, cabling etc. and internal, external pipeline during the repairing work shall be rectified / replaced by the contractor immediately at his own expense. University of Mumbai will not be responsible for any postal delay/loss in transit.

University Engineer reserves the right to reject all the tenders or any tender without assigning any reasons therefore and to relax or waive any of the condition stipulated in any of the tender that may be issued wherever necessary.


(S. V. Rane)
University Engineer
IPEMD, Fort/Kalina
University of Mumbai



Estimate

Name of work : Repairs and Painting in room no.138 on 1st floor at Fort Campus, University of Mumbai, Mumbai-32.

Sr. No.	SSR Item No.	Quantity	Description	Unit	Rate	5%	Amount
1	46.19	32.4	Removing cement tiles, or marble or polished shahabad floor or dado without bed concrete including stacking the materials as directed with all leads, lifts etc. complete	Square Metre	42	44.1	1428.84
2	46.06	32.4	Dismantling flat wooden or A.C. Sheet ceiling with frame work including stacking the materials as directed with all leads, lifts etc. complete	Square Metre	56	58.8	1905.12
3	32.33	7.5	Removing the existing cement plaster of any thickness without causing dust nuisance and stacking the debris upto a distance of 50 metres or spreading in the compound and cleaning the site etc. complete	Square Metre	49	51.45	385.88
4	32.02	7.5	Providing internal cement plaster 6 mm thick in a single coat in cement mortar 1:3 without neeru finish to concrete surface in all positions including scaffolding and curing etc. complete	Square Metre	197	206.85	1551.38
5	33.19	32.4	Providing sills of polished Kota stone 25 mm to 30mm thick, on a bed of 1:4 cement mortar including cement float, filling joints with slurry, curing, moulding edges, polishing and cleaning etc. complete.	Square Metre	1215	1275.75	41334.30
6	38.51	32.4	Providing and fixing in position Gypsum board false ceiling with 12.5 mm thick Gypsum boards, screwed/ fixed to the under structure of suspended G.I. Grid constructed and suspended from the main ceiling consisting of ceiling sections of size 25 x 50 mm maximum center to center distance of 600 millimetre perimeter channel and intermediate channels at maximum center to center distance 1200 millimetre galvanized grid should be fixed to reinforced cement concrete slab. The gypsum board should be fixed to galvanized iron grid with necessary screws. The boards should be taped and filled from underside to give smooth, seamless ceiling. The rate should include necessary additional ceiling sections and intermediate channels. Additional intermediate channels should be fixed to strap hangers for additional support to prevent strapping at every 1200 millimetre item to be completed in all respect including necessary sleeves for ducts finishing of joints cut outs, painting including labour, material, lifts etc. all complete.	Square Metre	1637	1718.85	55690.74
7	36.19	224.4	Scrapping the old plastered internal surface with sand paper and coating the entire surface with mixture of whitening or glue and linseed oil including scaffolding etc. complete as directed	Square Metre	34	35.7	8011.08
8	35.21	224.4	Providing and applying priming coat on concrete/ masonry/ Asbestos Cement plastered surfaces including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required etc. complete.	Square Metre	34	35.7	8011.08
9	32.34	224.4	Providing and applying Two coats of wall care Putty on plastered surface and Ceiling and Walls to prepare surface even and smooth of approved make, etc complete	Square Metre	87	91.35	20498.94



Sr. No.	SSR Item No.	Quantity	Description	Unit	Rate	5%	Amount
10	36.13	224.4	Providing and applying plastic emulsion paint of approved quality, colour and shade to old surface in three coats including scaffolding, preparing the surface. (excluding primer coat) etc. complete.	Square Metre	88	92.4	20734.56
11	35.07	4.05	Providing and applying two coats of synthetic enamel paint of approved colour to new /old structural steel work and wood work in buildings, including scaffolding if necessary, cleaning and preparing the surface (excluding primer coat) etc. complete.	Square Metre	89	93.45	378.47
12	34.05	30	Providing and applying French polish for required finish on previously polished wood including knotting, preparing the surfaces, scaffolding etc. complete as directed	Square Metre	118	123.9	3717.00
13	32.08	36	Providing internal cement plaster 20mm. thick in Single coats in cement mortar 1:3 without neeru finish, to concrete, brick surface, in all positions including scaffolding and curing etc. complete	Square Metre	376	394.8	14212.80
14	MuCir DSR 15-16 P-195/1-37.	1	Removing any kind of debris including loading in truck and conveying day to day basis to approved dumping point i.e. @ urban / industry loading sreading etc.complete with all leads and lifts (lead 52 km)	trip	4994	4994	4994.00
Total Amount							1,82,854.18
Add 12% GST							21,942.50
Total Amount I/c Tax							2,04,796.68

Estimate Prepared & Checked by:

University Engineer
(University of Mumbai)

We quote _____ % i.e. _____ percentage (in words)
above/below/at par than estimated cost of Rs. 1,82,854/-

Rubber stamp of firm

(Signature of Contractor)